

PALO ALTO MEDICAL CENTER

Sunnyvale, CA



This project was an existing medical facility in a residential neighborhood. DGC was contracted to demolish the existing medical building and site improvements, excavate for a new structure, approx. 150,000 sf two level basement, (approx. 80,000 cy), install utilities and reconstruct both the on-site parking lot and offsite street. Excavation along the north property line required installation of internal rakers, which required excavating small confined areas between rakers to achieve contract compliance. DGC also performed the excavation for foundation elements within the building limits. This project was particularly challenging, as the neighborhood was not supportive of the project and limited site access in a very restrictive manner however, a successful project for DGC and DPR.

| PROJECT DETAILS | REFERENCE |
|---|--|
| Acreage: 3 acres | Loyd Ackerman, Project Manager |
| Scheduled completion date: January 2011 | DPR Construction |
| Actual completion date: July 2013 | Tel # 650-474-1450 |
| Final cost: \$4,025,071 | loyda@dprinc.com |